1/23/08 Brian 818-1330
- William Corso -

John Obrey
Obrey Insurance
John@obreyinsurance.com

called Dean Savramis -
1 617 956-7564 (not in)
↓ receptionist
↳ David @ Fema
Daisy Sweeney
617 832-4788

do photos

elevation certificate is for building

Bank requiring flood insurance
limited coverage -

used.

7/25/08 544 ESCORT

Found & Bob'd Cloud Tops Brass

14.73 ← 17.14 →
0.23 −2.18

BOLT X HYD RM 10

12.13	−0.03	4.98
14.13	+1.97	"
10.08	−2.08	"
10.29	−1.87	"
10.20	−0.46	6.4
9.76	−1.49	5.8
18.03	+1.14	0.25
19.81	+2.67	0.00
20.84	+3.70	0.00
20.79	+3.65	0.00
18.96	+1.82	0.0
13.78	−3.13	0.23
(11.71)		
11.75	−0.41	4.9
14.73	−2.18	0.2

FL ELEV UP 5" ± FROM DECK

LAG = 1' LOWER THAN SW COR

SW COR 8.7

.73 SCS TBM 12

END COR BLDG NE

END SE COR BLDG

@ GAR DOOR ± FLOOR EL FRONT

" " " " → UP 0.5 TO ELEVATE LEVEL

" " " " REAR

@ COR BLDG SW

DECK EL 1st (Ely Deck)

3rd Deck EL

5th Deck EL

4th " "

2nd Deck EL

SE COR LAMP POST NOW ± (PLAN PSA # 78)

CB OFF FRONT DOOR

X HYD BOLT CHK

PSA 15.45
− 11.70

3.75 DIFF

3.77 per my Notes OK



PLAN OF GROUND FLOOR & SITE

Scale - 1/8" = 1'-0"

I hereby certify that these drawings consisting of Plans on Sheets No. 2, 4, 5 and 6, and Elevations on Sheets No. 10 and 11 are accurate and as usual manner with the provisions of RSA 155-B:20(II). The building is not yet completed.

In the event that the Architect is not providing site supervision it shall be understood that he shall in no way be responsible for any discrepancies between the drawings and actual conditions on the site.

PLAN OF GROUND FLOOR & SITE			
"TOP OF THE SURF" CONDOMINIUM BUILDING FOR H.C.M. REALTY TRUST			
445 OCEAN BLVD., HAMPTON BEACH, N.H.			
BY	DATE	SHEET No.	FILE No.
E.B.M.	1981	2	981

EDWARD BENTON MILES Architect
EXETER, NEW HAMPSHIRE

D-10194 SHEET 1 of 6





6711
less 200 for interior walls
say 6500 sf enclosure

TOP OF THE SURF CONDOMINIUMS

FOR

H & M REALTY TRUST

IN

HAMPTON, N. H.

SCALE: 1" = 10' JAN. 1981 REVISED FEB 23, 1981

PARKER SURVEY ASSOC, INC.

EXETER & SEABROOK, N.H.

EXISTING SITE PLAN SHEET 1 OF 2 SHEETS

I, RICHARD A. PARKER JR. A DULY REGISTERED LAND SURVEYOR, HEREBY CERTIFY THAT THIS PLAN DEPICTS A SURVEY ACCURATELY AND THAT IT COMPLIES WITH R.S.A. 356-19:20(I) ALL PROPOSED BUILDINGS ON THIS SITE "NOT YET BUILT"

DATE 1-16-81

APPROVED BY THE HAMPTON PLANNING BOARD:

Chairman

DATE: 3/4/81

N/F D. McCARTHY & A. UNICE
R.C.R. 2226-1025
R.C.R. 2220-1551

MARSH

MARSH

CREEK

S 81-30-16 E 90.71

PAVED

SILL: 19.7
GARAGE
(1 UNIT OVER)

OVERHANG

STAIRS

2 UNITS

N/F N.D. CAMPEAU
R.C.R. 2156-345
R.C.R. 1951-408

CABIN
2 UNITS

SILL: 15.72

SEWER INTO GRD

FLOOD LIGHT

CABIN
2 UNITS
SILL: 15.75

CABIN
2 UNITS

SILL: 15.75

SEWER INTO GRD

2 UNITS

PORCH

STEPS

SHRUBS

EDGE OF PAVEMENT

3 UNITS

SILL: 17.99

FLOOD LIGHT

PORCH

SHRUBS

N/F A. & P. WICKS
R.C.R. 2137-031
R.C.R. 1716-040

N 05-14-30 E 71.33

S 09-36-23 W 204.53

POLE

PAVEMENT 14.77

8" SPRUCE

15

19.74

GAS LINE

HUMP

14.8

WOOD LT POST W/LIGHT

N/F F.W. HOULE

PAVED DRIVE

SEA DEN MOTEL

W. WATER

S. SEWER

SILL 16.50

FENCE 1 EDGE PAVEMENT

2" OVERHANG

S. ACCESS

TULLER ACRES

PAVEMENT 15.78

¾ PIPE TO

SIGN

SPOT EL

19.7

WOOD LT POST W/LIGHT

CONC. WALL

SIDEWALK

CALCULATED N 86-49-32 W 75.06 SIDEWALK

SEE R.C.R. 1396-052

CONC. WALL

BENCH MARK

SPOT EL

SPOT EL

DRAIN

SPOT EL

SPOT EL

SPOT EL

mark 11m 81

TOP OF THE SURF CONDOMINIUMS
FOR
H. & M. REALTY TRUST
IN
HAMPTON, N. H.

SCALE: 1" = 10' JAN. 1981 REVISED FEB. 25, 1981
PARKER SURVEY ASSOC., INC.
EXETER & SEABROOK, N.H.

PROPOSED SITE PLAN SHEET 2 OF 2 SHEETS (OVERLAY)

I, RICHARD N. PARKER JR., A NEW HAMPSHIRE REGISTERED LAND SURVEYOR, HEREBY CERTIFY THAT THIS PLAN (SHEETS 1 & 2) IS ACCURATE AND THAT IT COMPLIES WITH R.S.A. 356-B:15 (I) (B) (2). ALL PROPOSED BUILDINGS ON THIS SITE ARE AS SHOWN.
DATE 9/9/81

APPROVED BY THE HAMPTON PLANNING BOARD
DATE: 9/9/81

PROFILE - DRAINAGE TRENCH (NOT TO SCALE)

PROPOSED 15 UNIT CONDOMINIUM BUILDING

SEE FLOOR PLANS FOR UNIT, COMMON & LIMITED COMMON DESIGNATIONS

PAVED DRIVE

PROPOSED DRAINAGE TRENCH - SEE PROFILE

EDGE OF PAVEMENT

GRASS

STEPS

OCEAN BOULEVARD

NOTES:
1. ALL AREAS OUTSIDE BUILDING TO BE COMMON EXCEPT PARKING.
2. ALL PARKING SPACES TO BE LIMITED COMMON. SPACES 1 THROUGH 21 TO BE 9' BY 18'. SPACES 22 THROUGH 30 ARE AS SHOWN ON FLOOR PLANS.
3. ALL EXTERIOR LIGHTING TO BE DIFFUSED.

LEGEND:
- PROPOSED SHRUBS
- 15.5 PROPOSED SPOT ELEVATIONS
- EXTERIOR OVERHEAD LIGHT
- LIGHT POST WITH LIGHT

LOCUS MAP - NOT TO SCALE

9.76 GND
10.12 CATCH BASIN
* DECK 20.8
FLOOR 21.2
NEXT FLOOR 21.1
LAG 8.76
8.71 LAG
IF DROP TO MATCH SCS TBM 12 GAR = 10.1
GAR 10.29
Elevator 10.8 Level
10.7 Mechanics
20.8 * DECK
10.08
* DECK 19.8
* DECK 19.0
* DECK 18.0
14.0 H LAG
14.1 GND
12.1 GND
13.78 SE COR LAMPPOST SCS TBM #78 See PSA PLAN EL 13.73
RM 10 + X CUT BOLT HYD

D10041 | SHEET 2 OF 2

4176 SHEET 2 OF 2 OVERLAY

NATIONAL FLOOD INSURANCE PRO

ROCKINGHAM COUNTY,
NEW HAMPSHIRE
(ALL JURISDICTIONS)

PANEL 441 OF 681

(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
HAMPTON, TOWN OF	330132	0441	E

Notice to User: The **Map Number** shown below should be used when placing map orders; the **Community Number** shown above should be used on insurance applications for the subject community.

MAP NUMBER
33015C0441E

EFFECTIVE DATE
MAY 17, 2005

Federal Emergency Management Agency

BENCH MARK DESCRIPTIONS

Number	Description and Elevation (ft. msl.) 1/
SCS-TBM-10A	Approximately 0.5 mile south of Winnacunnet Road, along Ocean Boulevard, in front of the Vista Motel, the top of a NHDPW&H right-of-way marker that is set in the sidewalk. Elev. 8.07
SCS-TBM-11	Approximately 0.6 mile south of Winnacunnet Road, along Ocean Boulevard, on top of the southeast corner of the base of lamp 74 and about 1.65 ft. above the sidewalk. Elev. 14.42
SCS-TBM-12	Approximately 0.7 mile south of Winnacunnet Road, along Ocean Boulevard, on the top of the southeast corner of the base of lamp 78 and about 1.65 ft. above the sidewalk. Elev. 13.73
SCS-TBM-13	Approximately 0.8 mile south of Winnacunnet Road, along Ocean Boulevard, on the top of the southeast corner of the base of lamp 82 and about 1.65 ft. above the sidewalk. Elev. 13.70
SCS-TBM-14	Approximately 0.85 mile south of Winnacunnet Road, along Ocean Boulevard, on the top of the southeast corner of the base of lamp 86 and about 1.65 ft.

For community map revision history prior to countywide mapping, refer to the Community Map History table located in the Flood Insurance Study report for this jurisdiction.

To determine if flood insurance is available in this community, contact your insurance agent or call the National Flood Insurance Program at 1-800-638-6620.

MAP SCALE 1" = 500'

250 0 500 1000 FEET

150 0 150 300 METERS

NFIP

NATIONAL FLOOD INSURANCE PROGRAM

PANEL 0441E

FIRM

FLOOD INSURANCE RATE MAP

ROCKINGHAM COUNTY, NEW HAMPSHIRE (ALL JURISDICTIONS)

PANEL 441 OF 681

(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
HAMPTON, TOWN OF	330132	0441	E

Notice to User: The **Map Number** shown below should be used when placing map orders; the **Community Number** shown above should be used on insurance applications for the subject community.

MAP NUMBER 33015C0441E

EFFECTIVE DATE MAY 17, 2005

Federal Emergency Management Agency



BENCH MARK DESCRIPTIONS

Number	Description and Elevation (ft. msl.) 1/
SCS-TBM-10A	Approximately 0.5 mile south of Winnacunnet Road, along Ocean Boulevard, in front of the Vista Motel, the top of a NHDPW&H right-of-way marker that is set in the sidewalk. Elev. 8.07
SCS-TBM-11	Approximately 0.6 mile south of Winnacunnet Road, along Ocean Boulevard, on top of the southeast corner of the base of lamp 74 and about 1.65 ft. above the sidewalk. Elev. 14.42
SCS-TBM-12	Approximately 0.7 mile south of Winnacunnet Road, along Ocean Boulevard, on the top of the southeast corner of the base of lamp 78 and about 1.65 ft. above the sidewalk. Elev. 13.73


EXISTING
PAVED
PARKING
SURFSIDE 30
CONDOMINIUM
EXISTING
BUILDING
FLOOR ELEV: 10.40
N89°57'00"W
N82°17'00"E
42.00'
FNDIP
FNDRRSPK
SETPK
GAR
GAR
LOT
5,276 S.F.
0.12 Ac.
HSE**
HSE**
HSE
HSE
CTOOP
PORCH
ROOF
POST
FNDNHHB
N01°37'00"E
90.80'
N10°56'08"E
83.41'
POST & RAIL FENCE
EXISTING
RIM EL
8.68
(NORTHBOUND)
NH-HB269
SETSPK
17.73
1"=30'

BM COND HEAD OF SURVEY 271-2746 at Seawall ISLAND NGVD 1929 3.03 higher than MLW

=3.98 higher than MLW at Hampton Harbor

OLD INFO

APPENDIX B

BENCH MARK DESCRIPTIONS

Number	Description and Elevation (ft. msl.)[1/]
NHDPW&H BM-577A	At the Exeter-Hampton Expressway bridge over Tide Mill Creek, in the southeast corner of the wheel guard, a standard disk. Elev. 12.14
SCS-TBM-1	Approximately 0.25 mile west of the Hampton Sewerage Disposal Plant, along Tide Mill Road, a nail and disk set in the base of NET&T pole 516. Elev. 8.47
SCS-TBM-2	Approximately 0.15 mile west of the Hampton Sewerage Disposal Plant, along Tide Mill Road, a nail and disk set in the base of NET&T pole 7 and E&HE 522. Elev. 10.99
SCS-TBM-5	Along the power lines that run from the Hampton Sewerage Disposal Plant to Winnacunnet Road, a nail and disk set in the base of pole 429. Elev. 12.37
SCS-TBM-6	Approximately 0.15 mile west of Ocean Boulevard along Winnacunnet Road, across from Lomazzo's Restaurant, a nail and disk set in the base of pole 77 562. Elev. 8.32
SCS-TBM-7	Approximately 0.1 mile north of Winnacunnet Road, along Kings Highway, a nail and disk set in the base of pole 870 136. Elev. 8.89
SCS-TBM-8	At the southwest corner of the intersection of Ocean Boulevard and Winnacunnet Road, a nail and disk set in the base of NET&T pole 64-2548. Elev. 8.12
SCS-TBM-9	Approximately 0.2 mile south of Winnacunnet Road, along Ocean Boulevard, about 200 ft. south of Marshlands Motel, a nail and disk set in the base of NET&T pole 54 2538. Elev. 7.64
SCS-TBM-10	Approximately 0.35 mile south of Winnacunnet Road, along Ocean Boulevard, in front of Little Jacks Drive-In, a nail and disk set in the base of pole S 2688. Elev. 8.43

ELEVATION REFERENCE MARKS

REFERENCE MARK	ELEVATION IN FT. (NGVD)[1]	DESCRIPTION OF LOCATION
RM 6	16.68	Railroad spike set in pole No. 2956 in southeast corner of intersection of Landing Road and State Route 51.
RM 7	42.53	USC&GS disk stamped "P32 1943" in center of traffic island in junction of Winnacunnet Road and Locke Road.
RM 8	7.93	Chiseled square on granite cap header of culvert on south side of State Route 101C, approximately 0.25 mile west of junction with US Route 1A.
RM 9	12.14	NHDPW&H disk stamped "R65" on southwest side of State Route 51 bridge over Mill Creek.
RM 10	14.73	File cut "X" on bolt on fire hydrant in parking median of US Route 1A, approximately 0.3 mile northeast of junction with State Route 51.

[1] National Geodetic Vertical Datum of 1929

OLD INFO
10-15 YRS

Hampton River Entrance (Cont'd.)

Mean low water at Hampton River Entrance is based on 5 months of records, July - November 1931, reduced to mean values. Elevations of other tide planes referred to this datum are as follows: 1941-59 tidal epoch.

	Feet
Mean high water	8.30
Mean tide level — NGVD 29	4.15 — 3.77
Mean low water	0.00

The estimated highest water level to the nearest * half foot is ~~12~~ feet above mean low water. The estimated lowest water level to the nearest half foot is 3½ feet below mean low water.

* ESTIMATED highest water level compared with Published Mean to the nearest half foot is 13.0 feet above mean low water
Preliminary Value

8.30
3.77
4.53 mean high tide


EEL
DITCH (TIDAL)
"REF MAP 255-19"
SPRING MARSH
EXETER & HAMPTON ELEC. CO.
POLE LINE
MARSH LINE
ANCHOR COURT
(PRIVATE WAY)
ANCHOR ST.
PRIVATE
OCEAN
BOULEVARD
ATLA
27
0.56 A
28
0.41
29
0.47 A
1
3.89 A
31
0.15 A
32
0.09 A
33
0.09 A
14
0.28 A
48
0.10 A
49
0.09 A
8
1.20 A
15
0.09 A
16
.04 A
17
0.11 A
34
0.04 A
35
0.04 A
36
0.03 A
47
0.16 A

Harm MAIL TO Box 10

ROCKINGHAM COUNTY REGISTRY OF DEEDS

STATE OF NEW HAMPSHIRE
DEPARTMENT OF REVENUE ADMINISTRATION
REAL ESTATE TRANSFER TAX
3 THOUSAND 5 HUNDRED AND 25 DOLLARS
08 2107 327764 $3535.00

048025

Property Address: 445 Ocean Boulevard Unit 10, Top of the Surf Condominium, Hampton, NH 03842

2007 AUG 21 AM 9:44

FORECLOSURE DEED

Deutsche Bank National Trust Company, as Trustee for Long Beach Mortage Loan Trust 2006-11, a corporation duly established under the laws of the United States of America and having a usual place of business at P.O. Box 1093, MS: N 01 02 01, Northridge, CA 91328-1093, holder of the following mortgage given by:

Stanley Upson Jr to Washington Mutual Bank, dated October 30, 2006 and recorded with the Rockingham County Registry of Deeds at Book 4727, Page 1419

By power conferred by said Mortgage and the laws of the State of New Hampshire and in consideration of the sum of TWO HUNDRED THIRTY-FIVE THOUSAND AND 00/100 ($235,000.00) DOLLARS grants to Deutsche Bank National Trust Company, as Trustee for Long Beach Mortage Loan Trust 2006-11 of P.O. Box 1093, MS: N 01 02 01, Northridge, CA 91328-1093, that portion of the Premises conveyed by said Mortgage and described more particularly in Exhibit "A" attached hereto.

Executed this 19 day of July, 2007.

Deutsche Bank National Trust Company, as Trustee for Long Beach Mortage Loan Trust 2006-11 by Washington Mutual Bank as successor in interest to Long Beach Mortgage Company, its attorney in fact"

By: _____
Peter Read - AVP
July 19, 2007

Dakota, ss.

On this 19 day of July 2007, before me, the undersigned notary public, personally appeared Peter Read, proved to me through satisfactory evidence of identification, which were (personal knowledge), to be the person whose name is signed on the preceding or attached document, and acknowledged to me that (he) (she) signed it voluntarily for its stated purpose.

Capacity: (as AVP

for Deutsche Bank National Trust Company, as Trustee for Long Beach Mortage Loan Trust 2006-11 by Washington Mutual Bank as successor in interest to Long Beach Mortgage Company, its attorney in fact")

_____ (Affix Seal)
Notary Signature

My commission expires: 1/31/11

Matthew Allan Baneszewski
NOTARY PUBLIC - MINNESOTA
MY COMMISSION
EXPIRES JAN. 31, 2011

EXHIBIT A

A certain tract of land, with the buildings thereon, situate in the City of Hampton, County of Rockingham, and State of New Hampshire being known and designated as Lot Unit No. 10 of the Top of the Surf Condominium, Hampton, N.H., the site plan of which was duly recorded with the Rockingham Registry of Deeds as Plan No. D-10041, to which plan reference is hereby made for a more specific description of the premises.

Together with the Unit's undivided percentage interest in the common areas and facilities of the Condominium, as further outlined in the above-mentioned site plan.

The premises are conveyed subject to all easements, restrictions, buildings and zoning laws, agreements, rights of way, and encumbrances of record to the extent in force and applicable.

For title reference see deed recorded with said Registry of Deeds in Book 3984, Page 2226.

Brian Healey

William ??
$300 -

- Londonderry -

~~Stockton~~ Service
bhealy@~~cr~~pruverani.com

elevation cert
UNIT 10
Top Surf
D10041
by Thurs 8/31
Brian will come
& bring payment

Question

U.S. DEPARTMENT OF HOMELAND SECURITY
Federal Emergency Management Agency
National Flood Insurance Program

ELEVATION CERTIFICATE

OMB No. 1660-0008
Expires February 28, 2009

Important: Read the instructions on pages 1-8.

SECTION A - PROPERTY INFORMATION

For Insurance Company Use:
Policy Number
Company NAIC Number

A1. Building Owner's Name
Long Beach Mortgage Loan Trust 2006-11, Deutsche Bank Trust Company, trustee

A2. Building Street Address (including Apt., Unit, Suite, and/or Bldg. No.) or P.O. Route and Box No.
445 Ocean Boulevard Unit 10 (Top of the Surf Condominium)
City Hampton State NH ZIP Code 03842

A3. Property Description (Lot and Block Numbers, Tax Parcel Number, Legal Description, etc.)
Tax Map 266 Lot 28 Unit 10, Rockingham County Registry of Deeds Book 4835 Page 0536

A4. Building Use (e.g., Residential, Non-Residential, Addition, Accessory, etc.) Residential condominium

A5. Latitude/Longitude: Lat. 42d55'06.2"N Long. 70d48'12.5"W Horizontal Datum: ☐ NAD 1927 X NAD 1983

A6. Attach at least 2 photographs of the building if the Certificate is being used to obtain flood insurance.

A7. Building Diagram Number 7

A8. For a building with a crawl space or enclosure(s), provide
a) Square footage of crawl space or enclosure(s) 6500 sq ft
b) No. of permanent flood openings in the crawl space or enclosure(s) walls within 1.0 foot above adjacent grade 0
c) Total net area of flood openings in A8.b 0 sq in

A9. For a building with an attached garage, provide:
a) Square footage of attached garage n/a sq ft
b) No. of permanent flood openings in the attached garage walls within 1.0 foot above adjacent grade n/a
c) Total net area of flood openings in A9.b n/a sq in

SECTION B - FLOOD INSURANCE RATE MAP (FIRM) INFORMATION

B1. NFIP Community Name & Community Number	B2. County Name	B3. State
Hampton 330132	Rockingham	NH

B4. Map/Panel Number	B5. Suffix	B6. FIRM Index Date	B7. FIRM Panel Effective/Revised Date	B8. Flood Zone(s)	B9. Base Flood Elevation(s) (Zone AO, use base flood depth)
33015CO441	E	05/17/2005	05/17/2005	AE	9

B10. Indicate the source of the Base Flood Elevation (BFE) data or base flood depth entered in Item B9.
☐ FIS Profile X FIRM ☐ Community Determined ☐ Other (Describe)

B11. Indicate elevation datum used for BFE in Item B9: X NGVD 1929 ☐ NAVD 1988 ☐ Other (Describe)

B12. Is the building located in a Coastal Barrier Resources System (CBRS) area or Otherwise Protected Area (OPA)? ☐ Yes X No
Designation Date _____ ☐ CBRS ☐ OPA

SECTION C - BUILDING ELEVATION INFORMATION (SURVEY REQUIRED)

C1. Building elevations are based on: Construction Drawings* ☐ Building Under Construction* X Finished Construction
*A new Elevation Certificate will be required when construction of the building is complete.

C2. Elevations – Zones A1-A30, AE, AH, A (with BFE), VE, V1-V30, V (with BFE), AR, AR/A, AR/AE, AR/A1-A30, AR/AH, AR/AO. Complete Items C2.a-g below according to the building diagram specified in Item A7.
Benchmark Utilized FIRM RM 10 Vertical Datum NGVD 1929
Conversion/Comments _____

			Check the measurement used.
a)	Top of bottom floor (including basement, crawl space, or enclosure floor)	10.1	X feet ☐ meters (Puerto Rico only)
b)	Top of the next higher floor	21.1	X feet ☐ meters (Puerto Rico only)
c)	Bottom of the lowest horizontal structural member (V Zones only)	N/A	☐ feet ☐ meters (Puerto Rico only)
d)	Attached garage (top of slab)	N/A	☐ feet ☐ meters (Puerto Rico only)
e)	Lowest elevation of machinery or equipment servicing the building (Describe type of equipment in Comments)	10.7	X feet ☐ meters (Puerto Rico only)
f)	Lowest adjacent (finished) grade (LAG)	8.7	X feet ☐ meters (Puerto Rico only)
g)	Highest adjacent (finished) grade (HAG)	14.0	X feet ☐ meters (Puerto Rico only)

SECTION D - SURVEYOR, ENGINEER, OR ARCHITECT CERTIFICATION

This certification is to be signed and sealed by a land surveyor, engineer, or architect authorized by law to certify elevation information. *I certify that the information on this Certificate represents my best efforts to interpret the data available. I understand that any false statement may be punishable by fine or imprisonment under 18 U.S. Code, Section 1001.*

X Check here if comments are provided on back of form.

Certifier's Name Anne W. Bialobrzeski License Number NH #752

Title land surveyor Company Name Stockton Services

Address PO Box 1306 City Hampton State NH ZIP Code 03843-1306

Signature Anne W. Bialobrzeski Date 07/28/08 Telephone 603 929-7404

PLACE SEAL HERE
STATE OF NEW HAMPSHIRE
No. 752
ANNE W. BIALOBRZESKI
LICENSED LAND SURVEYOR
Anne W. Bialobrzeski
7/28/08

IMPORTANT: In these spaces, copy the corresponding information from Section A.	For Insurance Company Use:
Building Street Address (including Apt., Unit, Suite, and/or Bldg. No.) or P.O. Route and Box No. 445 Ocean Boulevard Unit 10 (Top of the Surf Condominium)	Policy Number
City Hampton State NH ZIP Code 03842	Company NAIC Number

SECTION D - SURVEYOR, ENGINEER, OR ARCHITECT CERTIFICATION (CONTINUED)

Copy both sides of this Elevation Certificate for (1) community official, (2) insurance agent/company, and (3) building owner.

Comments: Subject premises is Unit 10 only, 3rd floor unit (including garage level).
Mechanics at garage level = elevator only. Mechanics specific to units are housed in respective units.
Next higher floor elevation shown is at rear of building only (portion housing subject premises). Unit floor elevations step down toward street to elev 18.4.
Photos for insurance application attached.

Signature Date 07/28/08

X Check here if attachments

SECTION E - BUILDING ELEVATION INFORMATION (SURVEY NOT REQUIRED) FOR ZONE AO AND ZONE A (WITHOUT BFE)

For Zones AO and A (without BFE), complete Items E1-E5. If the Certificate is intended to support a LOMA or LOMR-F request, complete Sections A, B, and C. For Items E1-E4, use natural grade, if available. Check the measurement used. In Puerto Rico only, enter meters.

E1. Provide elevation information for the following and check the appropriate boxes to show whether the elevation is above or below the highest adjacent grade (HAG) and the lowest adjacent grade (LAG).
a) Top of bottom floor (including basement, crawl space, or enclosure) is _____.____ ☐ feet ☐ meters ☐ above or ☐ below the HAG.
b) Top of bottom floor (including basement, crawl space, or enclosure) is _____.____ ☐ feet ☐ meters ☐ above or ☐ below the LAG.

E2. For Building Diagrams 6-8 with permanent flood openings provided in Section A Items 8 and/or 9 (see page 8 of Instructions), the next higher floor (elevation C2.b in the diagrams) of the building is _____.____ ☐ feet ☐ meters ☐ above or ☐ below the HAG.

E3. Attached garage (top of slab) is _____.____ ☐ feet ☐ meters ☐ above or ☐ below the HAG.

E4. Top of platform of machinery and/or equipment servicing the building is _____.____ ☐ feet ☐ meters ☐ above or ☐ below the HAG.

E5. Zone AO only: If no flood depth number is available, is the top of the bottom floor elevated in accordance with the community's floodplain management ordinance? ☐ Yes ☐ No ☐ Unknown. The local official must certify this information in Section G.

SECTION F - PROPERTY OWNER (OR OWNER'S REPRESENTATIVE) CERTIFICATION

The property owner or owner's authorized representative who completes Sections A, B, and E for Zone A (without a FEMA-issued or community-issued BFE) or Zone AO must sign here. *The statements in Sections A, B, and E are correct to the best of my knowledge.*

Property Owner's or Owner's Authorized Representative's Name

Address City State ZIP Code

Signature Date Telephone

Comments

☐ Check here if attachments

SECTION G - COMMUNITY INFORMATION (OPTIONAL)

The local official who is authorized by law or ordinance to administer the community's floodplain management ordinance can complete Sections A, B, C (or E), and G of this Elevation Certificate. Complete the applicable item(s) and sign below. Check the measurement used in Items G8. and G9.

G1. ☐ The information in Section C was taken from other documentation that has been signed and sealed by a licensed surveyor, engineer, or architect who is authorized by law to certify elevation information. (Indicate the source and date of the elevation data in the Comments area below.)

G2. ☐ A community official completed Section E for a building located in Zone A (without a FEMA-issued or community-issued BFE) or Zone AO.

G3. ☐ The following information (Items G4.-G9.) is provided for community floodplain management purposes.

G4. Permit Number	G5. Date Permit Issued	G6. Date Certificate Of Compliance/Occupancy Issued

G7. This permit has been issued for: ☐ New Construction ☐ Substantial Improvement

G8. Elevation of as-built lowest floor (including basement) of the building: _____.____ ☐ feet ☐ meters (PR) Datum

G9. BFE or (in Zone AO) depth of flooding at the building site: _____.____ ☐ feet ☐ meters (PR) Datum

Local Official's Name Title

Community Name Telephone

Signature Date

Comments

☐ Check here if attachments

Building Photographs

See Instructions for Item A6.

Building Street Address (including Apt., Unit, Suite, and/or Bldg. No.) or P.O. Route and Box No. 445 Ocean Boulevard Unit 10 (Top of the Surf Condominium)	For Insurance Company Use: Policy Number
City Hampton State NH ZIP Code 03842	Company NAIC Number

If using the Elevation Certificate to obtain NFIP flood insurance, affix at least two building photographs below according to the instructions for Item A6. Identify all photographs with: date taken; "Front View" and "Rear View"; and, if required, "Right Side View" and "Left Side View." If submitting more photographs than will fit on this page, use the Continuation Page, following.

Front View

Rear View